

2018 Bond

Gollihar Road: Greenwood to Crosstown

Project Fact Sheet



PROJECT DESCRIPTION:

The project will reconstruct Gollihar Road from Greenwood Drive to the Crosstown Expressway. The existing roadway will be demolished and rebuilt with new concrete pavement, curb and gutter, sidewalks, ADA-compliant curb ramps, signage, pavement markings, RTA improvements, street light improvements, and traffic and pedestrian signal improvements. In addition to surface improvements, the Project includes stormwater, water, wastewater, and gas infrastructure improvements.

PROJECT FACTS

Project Consultant Architect: Ardurra Group, Inc.

City Project Manager: Diana Briseno

Contractor: Bay, LTD

Construction Inspector: Brian Skinner (361) 660-5052

Award Date: October 2022

Construction Start: February 2023

Anticipated Completion: November 2024

Total Project Value: \$10.1M

Additional Notes/Details:

- The current posted speed limit of 30 MPH will remain the same.
- The eleven (11) RTA bus stops along the Project will remain.
- The stormwater improvements include replacing all existing curb inlets, replacing deficient RCP lines, replacing CMP lines with RCP, replacing deficient junction boxes, and adjusting manhole lids.
- Proposed water improvements include the abandonment of the 6" waterline, removal of the existing 12" ACP line, and replacement with 12" PVC.
- Wastewater improvements include wastewater pipe bursting, removal of an existing wastewater manhole, rehab of eight (8) existing wastewater manholes with fiberglass liners, installation of a new 12" SDR 26 PVC wastewater line, and installation of a steel-cased wastewater line through a storm junction box.
- Proposed gas improvements include the new 8" gas line and conflict resolution, as required.