

2018 BOND

18040A South Oso Parkway

South Staples to South Oso Parkway

Project Fact Sheet



PROJECT DESCRIPTION:

The project scope encompasses the construction of South Oso Parkway from South Staples Street to South Oso Parkway, with a 2-lane roadway with new asphalt pavement, demolition of existing infrastructures, installation of curb and gutter, sidewalks, speed humps, ADA-compliant curb ramps, signage, pavement markings, illumination, storm sewer improvements, water line adjustments, and gas line adjustments with the addition of a paved parking lot for the botanical gardens.

PROJECT FACTS

Project Consultant Architect: Thomas Tiffin, P.E., Munoz Engineering

City Project Manager: Dazhi Sun, Ph.D., P.E.

Contractor: A. Ortiz Construction & Paving

Construction Inspector: Alex Mortera

Award Date: August 2022

Anticipated Construction Start: October 2022

Anticipated Completion: September 2023

Total Project Value: \$1.3 Million

Additional Notes/Details:

- The new roadway section provides a connection from South Oso Parkway to South Staples Street and a new connection for Corpus Christi Botanical Gardens.
- In addition to the new roadway, the following scope of work will be completed:
 - Installation of ADA-compliant sidewalk with headwall, ADA ramps, and speed humps
 - A new Street Lighting Type A
 - Storm Water improvements: installation of curb and gutter, three grate inlets, two curb inlet, new 556 linear feet of stormwater line, park safety end treatment, stone riprap, re-grading the ditch, wrought iron fence extension
 - Water improvements: adjusting valve box height and existing 8" C900 water line crossing with fittings
 - Gas Lines Improvements: adjusting 100 linear feet of existing gas lines
 - Construction of a new HMA paved parking lot